


## 260.1165 | Floor Mounted Tub Filler With Hand Held Shower






## **SPECIFICATIONS:**

- Solid Brass construction includes valve
- Floor Mount Installation
- Hand Shower Flow Rate = 1.8 GPM @ 60 PSI w/ back flow prevention
- Diverter knob controls water flow between spout and hand held
- 8.0 GPM Spout Flow Rate
- Includes anti-scald ring located on cartridge

## **STANDARDS:**

• ASME A112.18.1 / CSA B125.1









## **Technical Diagram**

